



CYUSBS234

# USB-Serial Development Kit Guide

Doc. # 001-86632 Rev. \*\*

Cypress Semiconductor  
198 Champion Court  
San Jose, CA 95134-1709  
Phone (USA): 800.858.1810  
Phone (Intl): +1.408.943.2600  
<http://www.cypress.com>



## Copyrights

© Cypress Semiconductor Corporation, 2013. The information contained herein is subject to change without notice. Cypress Semiconductor Corporation assumes no responsibility for the use of any circuitry other than circuitry embodied in a Cypress product. Nor does it convey or imply any license under patent or other rights. Cypress products are not warranted nor intended to be used for medical, life support, life saving, critical control or safety applications, unless pursuant to an express written agreement with Cypress. Furthermore, Cypress does not authorize its products for use as critical components in life-support systems where a malfunction or failure may reasonably be expected to result in significant injury to the user. The inclusion of Cypress products in life-support systems application implies that the manufacturer assumes all risk of such use and in doing so indemnifies Cypress against all charges.

Any Source Code (software and/or firmware) is owned by Cypress Semiconductor Corporation (Cypress) and is protected by and subject to worldwide patent protection (United States and foreign), United States copyright laws and international treaty provisions. Cypress hereby grants to licensee a personal, non-exclusive, non-transferable license to copy, use, modify, create derivative works of, and compile the Cypress Source Code and derivative works for the sole purpose of creating custom software and or firmware in support of licensee product to be used only in conjunction with a Cypress integrated circuit as specified in the applicable agreement. Any reproduction, modification, translation, compilation, or representation of this Source Code except as specified above is prohibited without the express written permission of Cypress.

Disclaimer: CYPRESS MAKES NO WARRANTY OF ANY KIND, EXPRESS OR IMPLIED, WITH REGARD TO THIS MATERIAL, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Cypress reserves the right to make changes without further notice to the materials described herein. Cypress does not assume any liability arising out of the application or use of any product or circuit described herein. Cypress does not authorize its products for use as critical components in life-support systems where a malfunction or failure may reasonably be expected to result in significant injury to the user. The inclusion of Cypress' product in a life-support systems application implies that the manufacturer assumes all risk of such use and in doing so indemnifies Cypress against all charges.

Use may be limited by and subject to the applicable Cypress software license agreement.

CapSense® is a registered trademark of Cypress Semiconductor Corp. All other trademarks or registered trademarks referenced herein are property of the respective corporations.

## Flash Code Protection

Cypress products meet the specifications contained in their particular Cypress PSoC Data Sheets. Cypress believes that its family of PSoC products is one of the most secure families of its kind on the market today, regardless of how they are used. There may be methods, unknown to Cypress, that can breach the code protection features. Any of these methods, to our knowledge, would be dishonest and possibly illegal. Neither Cypress nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as 'unbreakable'.

Cypress is willing to work with the customer who is concerned about the integrity of their code. Code protection is constantly evolving. We at Cypress are committed to continuously improving the code protection features of our products.

# Contents



<b>Safety Information</b>	<b>5</b>
<b>1. Introduction</b>	<b>7</b>
1.1 Kit Contents .....	7
1.2 Getting Started.....	8
1.3 Additional Learning Resources.....	8
1.4 Technical Support.....	8
1.5 Document History .....	9
1.6 Documentation Conventions .....	9
1.7 Abbreviations .....	10
<b>2. Software Installation</b>	<b>11</b>
2.1 CYUSBS234 DVK Software .....	11
2.2 Install Hardware.....	14
2.3 Uninstall Software .....	14
<b>3. Kit Operation</b>	<b>15</b>
3.1 Default Switch and Jumper Settings .....	16
3.2 USB-Serial Enumeration.....	17
3.3 USB-Serial Configuration on Windows OS.....	19
3.3.1 Connecting CYUSBS234 DVK to Cypress USB-Serial Configuration Utility..	19
3.3.2 USB Configuration .....	21
3.3.3 UART Configuration .....	25
3.3.3.1 Test Procedure for CYUSBS234 DVK Configured as UART .....	28
3.3.3.2 Throughput Determination .....	30
3.3.4 I2C Configuration .....	32
3.3.4.1 Test Procedure for CYUSBS234 DVK Configured as I2C .....	35
3.3.5 SPI Configuration .....	38
3.3.5.1 Test Procedure for CYUSBS234 DVK Configured as SPI.....	42
3.3.6 CapSense Configuration .....	45
3.3.6.1 Test Procedure for CYUSBS234 DVK Configured for CapSense ...	49
3.3.7 Battery Charger Detection (BCD) Configuration .....	52
3.3.7.1 Test Procedure for CYUSBS234 DVK Configured for BCD.....	54
3.3.8 CYUSBS234 DVK Restore Default Configuration Settings.....	56
<b>4. Hardware</b>	<b>59</b>
4.1 Board Details .....	59
4.2 Theory of Operation.....	61
4.3 Functional Description .....	62
4.3.1 Features .....	62
4.3.2 Power-Supply System.....	63
4.3.3 LEDs .....	64

4.3.4	USB Connector .....	65
4.3.5	Serial Communication Block (SCB) .....	66
4.3.5.1	SCB Jumpers.....	66
4.3.5.2	RS-232 Interface.....	67
4.3.5.3	I2C Interface .....	69
4.3.5.4	SPI Interface .....	69
4.3.5.5	GPIO Header .....	70
4.3.6	CapSense Button .....	70
4.3.7	Battery Charger Detection.....	71
4.3.8	Reset Switch .....	72
<b>5.</b>	<b>Additional Information</b>	<b>74</b>
5.1	Using USB-Serial on a Mac OS .....	74
5.1.1	Using CYUSBS234 DVK in Communications Device Class (CDC) Mode .....	74
5.1.2	Using the CYUSBS234 DVK board in Vendor Mode .....	75
<b>A.</b>	<b>Appendix</b>	<b>76</b>
A.1	Schematic .....	76
A.2	CY7C65211 USB-Serial Design Guidelines .....	81
A.3	Troubleshooting Guide .....	84
A.4	Bill of Materials (BoM) .....	86

# Safety Information



## Regulatory Compliance

The CYUSBS234 USB-Serial Development kit is intended for use as a development platform for hardware or software in a laboratory environment. The board is an open-system design, which does not include a shielded enclosure. This kit may cause interference to other electrical or electronic devices in close proximity. In a domestic environment, this product may cause radio interference. In such cases, take adequate preventive measures. Also, do not use this board near any medical equipment or RF devices.

Attaching additional wiring to this product or modifying the product operation from the factory default may affect its performance and cause interference with other apparatus in the immediate vicinity. If such interference is detected, suitable mitigating measures must be taken.



The CYUSBS234 contains electrostatic discharge (ESD) sensitive devices. Electrostatic charges readily accumulate on the human body and any equipment, and can discharge without detection. Permanent damage may occur on devices subjected to high-energy discharges. Cypress recommends proper ESD precautions to avoid performance degradation or loss of functionality. Store unused CYUSBS234 boards in the protective shipping package.



### End-of-Life / Product Recycling

This kit has an end-of-life cycle after five years from the year of manufacturing mentioned on the back of the box. Contact your nearest recycler for discarding the kit.

## General Safety Instructions

### ESD Protection

ESD can damage boards and associated components. Cypress recommends that you perform procedures only at an ESD workstation. If an ESD workstation is not available, use appropriate ESD protection by wearing an antistatic wrist strap attached to the chassis ground (any unpainted metal surface) on the board when handling parts.

### Handling Boards

CYUSBS234 boards are sensitive to ESD. Hold the board only by its edges. After removing the board from its box, place it on a grounded, static-free surface. Use a conductive foam pad if available. Do not slide the board over any surface.



### Using Batteries

Use only the recommended rechargeable Li-ion battery. Check the polarity of the battery connector before connecting to the board.

# 1. Introduction



Thank you for your interest in the CYUSBS234 USB-Serial Development Kit (DVK). This DVK is designed as an easy-to-use kit, showcasing the unique features of Cypress's CY7C65211 USB-Serial bridge controller. This device includes CapSense®, Cypress's leading capacitive touch-sensing technology, and the Battery Charger Detection (BCD) feature, which is compliant with the USB Implementers Forum (USB-IF) Battery Charging Specification. This kit includes EEPROMs to demonstrate I2C and SPI, an RS-232 line-driver for UART, a CapSense touch button, and a Lithium ion (Li+) battery charger circuit.

CY7C65211 is the first full-speed USB-Serial bridge controller that offers a single-channel configurable serial interface (UART/I2C/SPI). The controller also features BCD and capacitive touch sensing at low suspend-state currents of 5  $\mu$ A. The controller is offered in a 4x4-mm, 24-pin QFN package to meet the dimensional requirements of portable devices.

## 1.1 Kit Contents

The CYUSBS234 kit contains the following items:

- CYUSBS234 DVK board
- Quick start guide
- USB standard-A to micro-B cable
- Jumper wires
- Extra jumpers
- 5-V power supply adapter
- CY7C65211-24LTXI sample silicon chips

Figure 1-1. Kit Contents



Inspect the contents of the kit; if you find any part missing, contact your nearest Cypress sales office for assistance or go to [www.cypress.com/go/support](http://www.cypress.com/go/support).

## 1.2 Getting Started

This kit guide helps you get acquainted with the CYUSBS234 DVK. The [Software Installation chapter on page 11](#) provides step-by-step instructions to install the CYUSBS234 DVK software. The [Kit Operation chapter on page 15](#) describes how the kit operates, and explains how to configure the CY7C65211 USB-Serial bridge controller using the Cypress USB-Serial Configuration Utility. The [Hardware chapter on page 59](#) discusses the kit hardware. The [Additional Information chapter on page 74](#) explains how to run the CYUSBS234 kit on a Mac OS. The [Appendix chapter on page 76](#) provides the schematics, layout, bill of materials (BoM), troubleshooting guidelines, and board layout design guidelines for the CY7C65211 USB-Serial bridge controller.

## 1.3 Additional Learning Resources

Visit the USB-Serial web page, [www.cypress.com/go/usbserial](http://www.cypress.com/go/usbserial) for additional learning resources in the form of datasheets and application notes.

## 1.4 Technical Support

For assistance, go to [www.cypress.com/go/support](http://www.cypress.com/go/support) or contact our customer support at +1 (800) 541-4736 Ext. 8 (in the USA) or +1 (408) 943-2600 Ext. 8 (International).



## 1.5 Document History

Revision	PDF Creation Date	Origin of Change	Description of Change
**	09/12/2013	MVTA	Initial version of kit guide.

## 1.6 Documentation Conventions

Table 1-1. Document Conventions for Guides

Convention	Usage
Courier New	Displays file locations, user entered text, and source code: C:\...cd\icc\
<i>Italics</i>	Displays file names and reference documentation: For example, <i>CYUSBS234 USB DVK.cysusb</i>
[Bracketed, Bold]	Displays keyboard commands in procedures: [Enter] or [Ctrl] [C]
File > Open	Represents menu paths: File > Open > New Project
<b>Bold</b>	Displays commands, menu paths, and icon names in procedures: Click the <b>File</b> icon and then click <b>Open</b> .
Times New Roman	Displays an equation: $2 + 2 = 4$
Text in gray boxes	Describes cautions or unique functionality of the product.

## 1.7 Abbreviations

The following table lists the abbreviations used in this kit guide.

Abbreviation	Definition
BCD	battery charger detection
CDC	communications device class
CDP	charging downstream port
CPHA	clock phase
CPOL	clock polarity
CTS	clear to send
DCD	data carrier detect
DCP	dedicated charging port
DSR	data set ready
DTR	data terminal ready
DVK	development kit
ESD	electrostatic discharge
I2C	Inter Integrated Circuit
LDO	low drop-out
PC	personal computer
PID	product ID
RI	ring indicator
RTS	request to send
SCB	serial communication block
SDP	standard downstream port
SPI	serial peripheral interface
SSN	slave select n
UART	universal asynchronous receiver transmitter
USB	universal serial bus
VID	vendor ID

## 2. Software Installation



### 2.1 CYUSBS234 DVK Software

Follow these steps to install the CYUSBS234 DVK software:

1. Download and install the CYUSBS234 DVK software from [www.cypress.com/go/CYUSBS234](http://www.cypress.com/go/CYUSBS234).

The CYUSBS234 DVK software is available in two different installer formats for download:


- a. **CYUSBS234 Kit ISO:** This file is a complete package, stored in a CD-ROM image format that can be used to create a CD, or extract using ISO extraction programs, such as WinZip or WinRAR. This file includes all the required software, utilities, drivers, hardware files, and user documents.
  - b. **CYUSBS234 Kit Setup:** This installation package contains the files related to the kit. It does not include the Windows installer, Microsoft .NET Framework, and Visual C++ redistributable packages. If these packages are not on your computer, the installer automatically downloads and installs them from the Internet.
2. Run **cyautorun.exe** to start the installation process.
  3. Click **Install CYUSBS234 DVK** to start the installation, as shown in [Figure 2-1](#).

Figure 2-1. Kit Installer Startup Screen




4. Select the folder to install the CYUSBS234 DVK-related files. Choose the directory and click **Next**.

Figure 2-2. Default Path for DVK Installation




5. The CYUSBS234 Kit ISO installer automatically installs the required software, if it is not present on your computer. The CYUSBS234 Kit Setup installer directs you to download the required software from the Internet.
6. Select the installation type. The drop-down menu has two options: **Typical** (installs all the required features) and **Custom**. Click **Next** after you select the installation type.

Figure 2-3. Installation Type Options




7. Read the Cypress License Agreement and make a selection based on the terms of the license agreement. Click **Next** to continue the installation.

Figure 2-4. Cypress License Agreement



8. When the installation begins, a list of packages appears on the installation page. A green check mark appears adjacent to every package after successful installation. If a message from Windows Security appears, accept the **Always trust software from Cypress Semiconductor** option and click **Install**.

Figure 2-5. Installation Page



9. Enter your contact information or select the **Continue Without Contact Information** check box. Click **Finish** to complete the CYUSBS234 DVK installation.

Figure 2-6. CYUSBS234 DVK Installation Complete



10. After the installation is complete, the kit contents are available at the following location:

<Install directory>\Cypress\CYUSBS234 DVK\1.0\

## 2.2 Install Hardware

This kit does not require any additional hardware installation.

## 2.3 Uninstall Software

You can uninstall the CYUSBS234 DVK software using one of the following methods:


1. Go to **Start > All Programs > Cypress > Cypress Update Manager**; click the **Uninstall** button.
2. Go to **Start > Control Panel > Programs and Features**; select the program **CYUSBS234 DVK 1.0 Rev\*\*** from the list and click the **Uninstall/Change** button.

### 3. Kit Operation



The CYUSBS234 kit demonstrates the features of the CY7C65211 USB-Serial bridge controller. The CYUSBS234 DVK board is designed to work at 5 V. [Figure 3-1](#) shows an image of the board with references to the onboard components.

Figure 3-1. CYUSBS234 DVK Board





### 3.1 Default Switch and Jumper Settings

The switches and jumpers on the CYUSBS234 DVK board are shipped with default settings for the USB bus-powered mode, serial interface in the UART mode, and CapSense functionality. The board is powered by the PC or the hub when it is connected by a USB standard-A to micro-B cable. [Figure 3-2](#) and [Table 3-1](#) provide the default configuration settings for the switches and jumpers.

Figure 3-2. Default Jumper and Switch Settings




Table 3-1. Default Settings

Switch/Jumper	Position/Pins to be Shorted	Function
SW1	Position 2-3	Power supply selection switch set to bus-powered operation
SW2	Position 2-3	Battery power cut-off
J3	OPEN	VBAT LED
J4	1 and 2	Battery charge enable control pin #0 (BCD0)
J7	1 and 2	Bus detect
J8	1 and 2	Battery charge enable control pin #1 (BCD1)
J17	2 and 4	SCB configured for UART
J18	1 and 2	SCB configured for UART
J19	2 and 4	SCB configured for UART
J20	2 and 4	SCB configured for UART
J21	2 and 4	SCB configured for UART
J22	1 and 2	SCB configured for UART
J23	Open	GPIO header
J28	2 and 3	CapSense watershield feature disabled
J29	1 and 2	VBUS detection



## 3.2 USB-Serial Enumeration

The CYUSBS234 DVK board connects to the PC by a USB standard-A to micro-B cable. The board enumerates as a composite USB device.

Follow these steps for device enumeration:

1. To power up the board:
  - a. **Self-powered mode** - Set SW1 to position 1-2 and connect the 5-V power-supply adapter to J1 on the board.
  - b. **Bus-powered mode** - Set the switch SW1 to position 2-3.
2. Connect the USB standard-A to micro-B cable to the PC and J2 on the board.
3. The PC detects the board and the software driver is automatically bound to the USB device.

**Note** If the driver installation is unsuccessful, run *setup.exe* from the following folders with administrative privileges:

```
<Install directory>\Cypress\CYUSBS234 DVK\1.0\driver\cyusb3
```

```
<Install directory>\Cypress\CYUSBS234 DVK\1.0\driver\cyusbserial
```

For more information, refer to the Cypress USB-Serial Driver Installation Guide at the following location: <Install directory>\Cypress\CYUSBS234 DVK\1.0\documentation\

Figure 3-3. Install Location of cyusb3 Driver





Figure 3-4. Install Location of cyusbserial Driver




**Note** If a "Welcome to the Found New Hardware Wizard" message appears, select the **Yes, this time only** option and click **Next** to continue the installation.

4. When the software drivers are successfully bound, the board enumeration is complete. The board appears as a composite device in the device manager of the Windows OS (to launch the device manager in Windows 7, go to **Start > Control Panel > Device Manager**), as shown in Figure 3-5.

- USB-Serial Adapter under CypressUSBConsoleWindowsDriver

- USB Serial Port (COM#) under Ports (COM & LPT)
- USB-Serial (Single Channel) Vendor MFG under Universal Serial Bus controllers

Figure 3-5. CYUSBS234 DVK Enumeration as Single UART in Device Manager



### 3.3 USB-Serial Configuration on Windows OS

Using the Cypress USB-Serial Configuration Utility, you can configure the onboard CY7C65211 USB-Serial bridge controller as a USB-UART bridge, a USB-I2C bridge, or a USB-SPI bridge. You can also use this utility to configure the CY7C65211 device for CapSense and BCD functionality according to your requirements. The following sections provide detailed descriptions about the device features and configurations.

By default, the CYUSBS234 DVK board is configured for the USB-UART bridge and CapSense functionality.

#### 3.3.1 Connecting CYUSBS234 DVK to Cypress USB-Serial Configuration Utility

Follow these steps to connect the device using the Cypress USB-Serial Configuration Utility:


1. Connect the USB standard-A to micro-B cable to your PC and the J2 connector on the board.
2. Set switch SW1 to position 2-3 for bus-powered operation.
3. Run the configuration utility from **Start > All Programs > Cypress > CYUSBS234 DVK > USB Serial Configuration Utility**.

For a detailed description about the configuration utility, refer to the *USB-Serial Configuration Utility User Guide* at the following location:


<Install directory>\Cypress\CYUSBS234 DVK\1.0\documentation

4. The following figure shows the startup screen of the Cypress USB-Serial Configuration Utility.

Figure 3-6. Configuration Utility Startup Screen




- Click the **Select Target** tab. Select the device from the drop-down menu and click **Connect**.

 Figure 3-7. Configuration Utility **Select Target** Tab


**Note** The “version” number shown in [Figure 3-7](#) may vary depending upon the latest firmware version on the USB-Serial bridge controller.

- A new tab with the connected device's default settings appears, as shown in [Figure 3-8](#). This tab allows you to modify the device configuration settings, which you can program into the device.


 Figure 3-8. Configuration Utility **USB** Tab


### 3.3.2 USB Configuration

The USB tab shows the current values of the board's configurable USB and system parameters. Follow these steps to view and modify the parameters for the USB configuration:

1. Follow steps 1 to 6 in the section [Connecting CYUSBS234 DVK to Cypress USB-Serial Configuration Utility on page 19](#) to connect the board to the Cypress USB-Serial Configuration Utility.
2. Click the **USB** tab.

Figure 3-9. Configuration Utility **USB** Tab



3. You can configure the following USB parameters using the Cypress USB-Serial Configuration Utility:
  - a. Vendor ID (VID)
  - b. Product ID (PID)
  - c. Power Mode (bus-powered or self-powered)
  - d. bMaxPower
  - e. Remote wake-up and Suspend
  - f. Manufacturer string
  - g. Product string
  - h. Serial number

#### ■ Vendor ID (VID) and Product ID (PID)

Default value: 0x04B4 and 0x0002

A 2-byte vendor ID and product ID must be set in hexadecimal format. The VID and PID options cannot be zero or empty. The Cypress VID/PID is programmed by default. To change this, uncheck the **Use Cypress VID/PID** option. Enter the VID and press the **[Tab]** or **[Enter]** key to enable and enter the PID.

### ■ Power Mode

Default value: Bus powered

The USB power mode can be set to either self-powered or bus-powered mode.

### ■ bMaXPower

Default Value: 100 mA

The USB device current requirement value can be set in the range 1 to 500 mA in steps of 2 mA units in bus-powered mode and 0 mA to 500 mA in steps of 2 mA units in self-powered mode.

### ■ Remote Wake-up and Suspend


Default value for Remote wake-up: Enabled

Default value for Suspend: Enabled

Default value for Power Enable: Not enabled (for this board)

Click the **Configure** button (next to **Remote Wake-up and Suspend** in the USB tab) to enable or disable Remote wake-up and Suspend.

Figure 3-10. Configure Remote Wake-up and Suspend Window



### Configurable options:

- ❑ Remote wake-up: When enabled, this option can be used to wake up the USB host from suspend state remotely from the attached device. By checking the **Invert Polarity** box, polarity of the wake-up pin can be inverted. J23.6 (GPIO header) on this board is a wake-up pin. To test the Remote wake-up functionality, follow this procedure:
  - Connect the Remote wake-up pin (J23.6) to GND (J23.10) using the provided jumper wire.
  - Connect the CYUSBS234 DVK board to a PC using USB standard A to micro-B cable.
  - Set the PC into sleep mode. When the PC enters sleep mode, the USB host on the PC side suspends the connected CYUSBS234 DVK board.
  - By default, the Remote wake-up pin is active high. Disconnect the Remote wake-up pin (J23.6) from GND (J23.10) and touch TP10 (V3P3), as shown in [Figure 3-2](#). If the **Invert Polarity** option is selected, then connect the pin to GND to wake up the USB host from the Suspend state.
- ❑ Suspend: By checking this box, the Suspend option is enabled. When the USB bus enters the Suspend state, the suspend pin is asserted. By checking the **Invert Polarity** box, polarity of the Suspend pin can be inverted. J23.4 (GPIO header) on this board is a suspend pin.
- ❑ Power enable: The Power enable function is enabled by assigning a GPIO from the drop-down menu. When the USB-Serial bridge is configured by the host, this GPIO is asserted. In bus-powered embedded systems, to meet the USB 2.0 Specification requirements during Unconfigured and Suspend states, this pin can be used as a notification to control the power to the system. Refer to the *Configuration Utility User Guide* for more details about these options.

**Test Procedure for Suspend and Power Enable Pin.**

- a. Connect the CYUSBS234 DVK board to a PC using USB standard A to micro-B cable.
- b. Set the PC into sleep mode.
- c. Check the Suspend pin (J23.4) and Power Enable pin (selected GPIO which comes on external header J23) using a digital multimeter or digital storage oscilloscope. The Suspend pin goes low and Power enable pin goes high during sleep mode. (By default, the invert polarity is disabled. If the invert polarity is enabled, the Suspend pin goes high during sleep mode.)
- d. Wake up the PC using the Remote wake-up feature described in page 22, or using any other device such as a mouse or keyboard connected to the PC. When the PC becomes active, the Suspend pin goes high and power enable pin goes low.

**■ Manufacturer string**

Default value: Cypress Semiconductor

The Manufacturer string can be a value of up to 32 characters.

**■ Product string**

Default value: USB-Serial (Single Channel)

The Product string can be a value of up to 32 characters.

**■ Serial number string**

Default value: NULL (No serial number)

Select the check box to enter the serial number, which can be a value of up to 32 characters. If you do not require the serial number, deselect the check box.

**System**

The Configurable options are:

- a. VBUS voltage is 3.3 V
- b. VDDD voltage is less than 2 V
- c. Enable manufacturing interface
- d. I/O Level
- e. I/O Mode
- f. Program button
- g. Disconnect button

**■ VBUS voltage is 3.3 V**

Default value: Unchecked

This option must be checked if the VBUS pin is supplied with 3.3 V, and unchecked if the VBUS pin is supplied with 5 V. The board is designed only for 5-V VBUS operation. This option must always be unchecked for the board. The CY7C65211 device supports VBUS voltage range from 3.15 V to 5.25 V.

**■ VDDD voltage is less than 2 V**

Default value: Unchecked

The board is designed only for 5-V operation. This option must always be unchecked for the board. The CY7C65211 device supports VDDD voltage range from 1.71 V to 5.5 V.

**■ Enable manufacturing interface**

Default value: Checked

This option enables an additional vendor class manufacturing mode interface for reprogramming the device. For more information, refer to the Enable Manufacturing Interface section in the *Cypress USB-Serial Configuration Utility User Guide*.



- **I/O level**

Default value: CMOS

You can set the device's GPIO logic levels to either CMOS or LVTTTL.

- **I/O Mode**

Default value: Fast

You can set the device's GPIO edge transitions to either fast or slow for EMI considerations. For more information, refer to the GPIO AC Specifications table in the datasheet.

- **Program button**

After configuring all the device settings, the updated configuration settings must be programmed to the device. To program the device, click the **Program** button.

- **Disconnect button**

Click this button to disconnect the DVK from the configuration utility.

4. After configuring the USB and system parameters, click the **Program** button to save the changed USB parameters. On successful programming, the "Program Succeeded" message appears. Click **OK** to continue.
5. Click the **Disconnect** button to disconnect the board from the configuration utility.
6. Press the reset switch **SW3** on the board. The controller is reinitialized with the new parameters and the board re-enumerates, as shown in [Figure 3-5 on page 18](#).




### 3.3.3 UART Configuration

The CYUSBS234 DVK board is configured for the UART interface by default. The board can act as a USB-UART bridge to transfer and receive data between the device and the PC via terminal communication software, such as Hyperterminal or Tera Term.

Follow these steps to view and modify the parameters for the UART configuration:


1. Follow steps 1 to 6 of the section [Connecting CYUSBS234 DVK to Cypress USB-Serial Configuration Utility on page 19](#) to connect the board to the Cypress USB-Serial Configuration Utility.
2. Click the **SCB** tab. Select **UART** as the SCB mode from the drop-down menu.

Figure 3-11. Configuration Utility **SCB** Configuration Tab



3. Click the **Configure** button, as shown in [Figure 3-11](#), to configure the UART parameters.

Figure 3-12. **UART** Configuration parameters



You can configure the following UART parameters by using the Cypress USB-Serial Configuration Utility:

- a. Baud Rate
- b. Type
- c. Data Width
- d. Stop Bits
- e. Parity
- f. Drop packets on RX error
- g. Disable CTS and DSR pull-up during suspend

■ **Baud Rate**

Default value: 115200

You can set the baud rate for the UART in an editable drop-down combo box that lists the pre-defined, standard baud rates. You can also enter a specific baud rate in the combo box. The minimum and maximum baud rates supported by this board are 300 bps and 1 Mbps, respectively. The CY7C65211 device supports 3 Mbps, but the board limits the baud rate to 1 Mbps, due to the limitation of the RS-232 line driver (U5).

■ **Type**

Default value: 6 pin

You can set the UART type to:

- a. 2 pin (RXD and TXD pins)
- b. 4 pin (RXD, TXD, RTS, and CTS pins)
- c. 6 pin (RXD, TXD, RTS, CTS, DSR, and DTR pins)

■ **Data Width**

Default value: 8 bits

You can set the UART data width to either 7 bits or 8 bits.

■ **Stop Bits**

Default value: 1 bit

You can set the number of UART stop bits to either 1 bit or 2 bits.

■ **Parity**

Default value: None

You can set the parity for the UART data transfer to either None, Odd, Even, Mark, or Space.

■ **Drop packets on RX errors**

Default value: Unchecked

This parameter defines the behavior of the UART when an error is detected in the packet received (RX packet/byte). When this option is selected, the data packet/byte in the RX buffer is discarded.

■ **Disable CTS and DSR pull-up during suspend**


Default value: Checked

In an embedded system, this parameter can be checked to reduce system current consumption during Suspend state. This parameter disables CTS and DSR pull-up resistors in Suspend state to meet USB 2.0 Specification current requirements.

4. Click **OK** to close the **Configure UART Settings** window and return to the **SCB** tab.
5. Select **CDC** as the protocol in the drop-down menu.

6. Notification LEDs are set to None, by default. The notification LED pins are brought out on the external GPIO header J23. You can configure any GPIO as a notification LED by clicking the **Configure** button next to “Notification LED” in the **SCB** tab and connect an external LED to the assigned GPIO pin on the GPIO header J23.
7. After configuring the UART interface, click the **Program** button to save the changed SCB settings onto the controller. On successful programming, the “Program Succeeded” message appears. Click **OK** to continue.
8. Click the **Disconnect** button to disconnect the board from the configuration utility.
9. Press the reset switch **SW3** on the board. The controller is reinitialized with the new parameters and the board re-enumerates, as shown in [Figure 3-13](#).

Figure 3-13. CYUSBS234 DVK Board Enumeration as USB-UART Controller in Device Manager



10. The Cypress USB-Serial Configuration Utility is displayed, as shown in [Figure 3-7 on page 20](#).

### 3.3.3.1 Test Procedure for CYUSBS234 DVK Configured as UART

1. To test the functionality of the UART interface, set up the jumpers as listed in [Table 3-3](#) and shown in [Figure 3-14](#) and [Figure 3-15](#).

Table 3-2. Jumper Settings

Jumper	Pins to be Shorted	Function
J17	2 and 4	SCB_2 (Pin#21) configured for UART RTS
J18	1 and 2	SCB_0 (Pin#1) configured for UART RXD
J19	2 and 4	SCB_1 (Pin#20) configured for UART DSR
J20	2 and 4	SCB_3 (Pin#22) configured for UART CTS
J21	2 and 4	SCB_4 (Pin#23) configured for UART TXD
J22	1 and 2	SCB_5 (Pin#2) configured for UART DTR
J29	1 and 2	VBUS selection

Figure 3-14. SCB UART Jumpers






Figure 3-15. VBUS Selection Jumper



2. To check the functionality of the UART, you can perform a quick loopback test by interconnecting the DB9 connector pins with the jumper wires as follows:
  - J15.3-J15.2 (TXD of SCB to RXD of SCB)
  - J15.4-J15.6 (DTR of SCB to DSR of SCB)
  - J15.7-J15.8 (RTS of SCB to CTS of SCB)

Figure 3-16. Connection for Loopback Test




3. Open an instance of the serial emulation terminal, such as Tera Term, which you can install from the following location:
 

```
<Install directory>/Cypress/CYUSBS234 DVK/1.0/teraterm
```

4. In the **Tera Term: New Connection** window, click **Serial** and select **USB Serial Port (COM#)**, as shown in [Figure 3-17](#). Click **OK**.

**Note** To change the UART parameters, go to **Setup > Serial Port** in the Tera Term terminal.


Figure 3-17. Tera Term Connection



5. Connecting TXD to RXD enables the data to flow from the UART transmitter to the receiver, which is displayed on the same terminal, as shown in [Figure 3-18](#). This test procedure validates the functioning of the USB-UART bridge. If the local echo option is enabled, then the entered data appears twice on the terminal.

**Note** To enable the local echo option, go to **Setup > Terminal**. In the “Tera Term: Terminal Setup” window; check the **Local echo** box.

Figure 3-18. Tera Term Application: Loopback Test Output



**Note** This screenshot is captured without enabling Local echo.

### 3.3.3.2 Throughput Determination


Throughput is the average rate of successful data transfer over the UART channel. It is measured in bits/second. A PC application can be used to determine the throughput of an USB-Serial bridge controller. The CY7C65211 device supports 3 Mbps, but the actual reported throughput on a PC applica-

tion (Tera Term) will be less than 1 Mbps, due to RS-232 line driver limitation, protocol overhead, and PC application latency.

Follow these steps to determine the throughput of the USB-Serial bridge controller:


1. In the Tera Term window, go to **Setup > Serial Port**:
  - a. Enter '1000000' in the **Baud rate** drop-down combo box.
  - b. Select **Hardware** in the **Flow control** drop-down menu.
  - c. Click **OK**
2. Go to **Setup > Terminal > Receive** and select **CR+LF**. Click **OK** to continue.
3. Go to File menu. Select **Send File** from the drop-down menu, as shown in [Figure 3-19](#).

Figure 3-19. Sending the File



4. Select a file to be sent through **USB Serial Port (COM#)**. After the file is selected, the data transfer starts and the window is displayed, as shown in [Figure 3-20](#).
5. Number of bytes transferred per second determines throughput. The "Tera Term :Send File" window shows effective data throughput in Bytes/sec; multiply this value by 8 to get the throughput in bits/sec. Again, multiply this value by 2 to get the unidirectional throughput.

Figure 3-20. Throughput Determination






### 3.3.4 I2C Configuration

You can configure the CYUSBS234 DVK board for the I2C serial interface to function as a USB-I2C bridge. The onboard I2C EEPROM (operating in I2C slave mode) can be connected to the USB-Serial bridge controller, CY7C65211, to read and write data. The USB-Serial Test Utility can be used to read, write, and verify the contents of EEPROM from the PC. The Test Utility software is available as part of the CYUSBS234 kit installer.

Follow these steps to view and modify the parameters for the I2C configuration:


1. Follow steps 1 to 6 in the section [Connecting CYUSBS234 DVK to Cypress USB-Serial Configuration Utility on page 19](#) to connect the board to the Cypress USB-Serial Configuration Utility.
2. Click the **SCB** tab. Select **I2C** as the SCB mode from the drop-down menu.

Figure 3-21. **SCB** Configuration Tab



3. Click the **Configure** button, as shown in [Figure 3-21](#), to configure the I2C settings.

Figure 3-22. I2C Configuration Settings





You can configure the following I2C parameters by using the Cypress USB-Serial Configuration Utility:

- a. Frequency
- b. Mode
- c. Use as wake-up source (Slave mode only)
- d. Slave Address (Slave mode only)
- e. Enable clock stretching (Slave mode only)

■ **Frequency**

Default value: 100 kHz

You can set the operating frequency of the I2C master/slave from 1 kHz to 400 kHz in the drop-down menu.

■ **Mode**

Default value: Master

You can configure the I2C mode to either a master or a slave. To support the slave mode, contact [Cypress Technical Support](#).

■ **Slave Address**

Default value: 2

This option is available only in the I2C slave mode. The I2C slave address can be from 2 to 126 (in decimal) in increments of 2.

■ **Enable clock stretching**

Default value: Unchecked

This option is available only in I2C slave mode. You can use this option when there is a mismatch between the master and the slave clock frequency. Both master and slave can operate at the same frequency by enabling clock stretching.


■ **Use as wake-up source**

Default value: Disabled

This option is available only in I2C slave mode. USB-Serial bridge controller as I2C slave can be used as remote wake-up source to wake-up the USB host.

4. Click **OK** to close the **Configure I2C Settings** window and return to the **SCB** tab.
5. Select **Vendor** as the protocol in the drop-down menu.
6. Notification LEDs are set to None, by default for this board. The notification LED pins are brought out on the external GPIO header J23. You can configure any GPIO as a notification LED by clicking the **Configure** button next to "Notification LED" in the SCB tab and connect an external LED to the assigned GPIO pin on the GPIO header J23.
7. After configuring the I2C interface, click the **Program** button to save the changed SCB settings. On successful programming, the "Program Succeeded" message appears. Click **OK** to continue.
8. Click the **Disconnect** button to disconnect the board from the configuration utility.
9. Press the reset switch **SW3** on the board. The controller is reinitialized with the new parameters and the board re-enumerates, as shown in [Figure 3-23](#).

Figure 3-23. CYUSBS234 DVK Enumeration as USB-Serial Bridge Controller in Device Manager



10. The Cypress USB-Serial Configuration Utility is displayed, as shown in [Figure 3-7 on page 20](#).

### 3.3.4.1 Test Procedure for CYUSBS234 DVK Configured as I2C

1. To test the functionality of the I2C interface, set up the jumpers as listed in [Table 3-3](#) and shown in [Figure 3-24](#) and [Figure 3-25](#).

Table 3-3. Jumper Settings

Jumper	Pins to be Shorted	Function
J17	2 and 3	SCB_2 (Pin#21) configured for I2C SCL
J20	2 and 3	SCB_3 (Pin#22) configured for I2C SDA
J29	1 and 2	VBUS selection

Figure 3-24. SCB I2C Jumpers






Figure 3-25. VBUS Selection



2. Run the USB Serial Test Utility from **Start > All Programs > Cypress > CYUSBS234 DVK > USBSerialTestUtility**.
3. To use the default Cypress PID, change the **Product ID** to **0004**.


**Note** The user has the option to enter custom Vendor ID and Product ID.

Figure 3-26. Test Utility (VID and PID Selection)




4. The test utility lists the interfaces available on the board for the I2C interface. Click **OK**.

Figure 3-27. Test Utility (change of PID)




5. Enter an EEPROM page address within the range specified in the text box (0x0 to 0xFF) and click the **Write data** button. The status bar at the bottom of window displays the status of the data.

Figure 3-28. Test Utility Data Transfer




6. Click the **Read & verify data** button. When the written and read back data are the same, the "Data verification successful" message appears.

Figure 3-29. Test Utility Data Transfer Verification



7. Click **OK**. The "Data verification successful" message appears at the bottom of the window.

Figure 3-30. Test Utility Successful Data Transfer Verification



### 3.3.5 SPI Configuration


You can configure the CYUSBS234 DVK board for the SPI serial interface to function as a USB-SPI bridge. The onboard SPI EEPROM (operating in the SPI slave mode) can be connected to the CY7C65211 USB-Serial bridge controller, to read and write data. The USB-Serial Test Utility provided can be used to read, write and verify data from the PC. The Test Utility software is available as part of the CYUSBS234 kit installer.

Follow these steps to view and modify the parameters for the SPI configuration:

1. Follow steps 1 to 6 in the section [Connecting CYUSBS234 DVK to Cypress USB-Serial Configuration Utility on page 19](#) to connect the board to the Cypress USB-Serial Configuration Utility.


2. Click the **SCB** tab. Select **SPI** as the SCB mode from the drop-down menu.

Figure 3-31. Configuration Utility SCB Configuration Tab



3. Click the **Configure** button, as shown in [Figure 3-31](#), to configure the SPI settings.

Figure 3-32. SPI Configuration Settings



You can configure the following SPI parameters by using the Cypress USB-Serial Configuration Utility:

- a. Frequency
- b. Data width
- c. SPI mode
- d. Use as wake-up source (slave mode only)
- e. Protocol
- f. Enable select precede (TI Protocol only)



g. CPHA and CPOL mode (Motorola Protocol only)

h. SSN Toggle mode (Motorola Protocol only)

i. Bit order

■ **Frequency**

Default Value: 1 MHz

You can set the SPI operating frequency from 1 kHz to 3 MHz with increments of 1 Hz.

■ **Data width**

Default Value: 8 bits

You can set the SPI data width from 4 bits to 16 bits in the drop-down menu.

■ **SPI mode**

Default value: Master

You can configure the SPI mode to either a master or a slave. To support the slave mode, contact [Cypress Technical Support](#).

■ **Use as Wake-up source**

Default value: Disabled

This parameter is applicable only when the SPI mode is set to Slave.

■ **Protocol**

Default value: Motorola

You can select one of the three SPI protocols:

- ☐ Motorola
- ☐ Texas Instruments
- ☐ National Semiconductors

■ **Enable Select Precede**

Default status: Disabled

This parameter is applicable only when the SPI protocol is set to TI.

■ **CPHA and CPOL mode**

Default Value: Both Low

The CPHA (Clock Phase) and CPOL (Clock Polarity) parameters are available only when the SPI protocol is set to Motorola.

You can set the CPOL and CPHA values to either Low or High from the drop-down menu.

■ **SSN Toggle mode**

Default value: Continuous

This option is available only when the Protocol is set to Motorola.

You can set the SSN (Slave Select n) toggle mode to either Frame or Continuous. SPI EEPROM on the board supports only "Continuous" SSN Toggle mode.

■ **Bit Order**

Default value: MSB first

You can set the bit order to either MSB first or LSB first.

**Note** Refer to the *SPI Mode* section in the *Cypress USB-Serial Configuration Utility User Guide* for more information.


4. Click **OK** to close the **Configure SPI Settings** window and return to the **SCB** tab.

5. Select **Vendor** as the protocol in the drop-down menu.



6. Notification LEDs are set to None, by default for this board. The notification LED pins are brought out on the external GPIO header J23. You can configure any GPIO as a notification LED by clicking the **Configure** button next to "Notification LED" in the SCB tab and connect an external LED to the assigned GPIO pin on the GPIO header J23.
7. After configuring the SPI interface, click the **Program** button to save the changed SCB settings. On successful programming, the "Program Succeeded" message appears. Click **OK** to continue.
8. Click the **Disconnect** button to disconnect the board from the configuration utility.
9. Press the reset switch **SW3** on the board. The controller is reinitialized with the new parameters and the board re-enumerates, as shown in [Figure 3-33](#).

Figure 3-33. CYUSBS234 DVK Enumerates as USB-Serial Bridge Controller in Device Manager



10. The Cypress USB-Serial Configuration Utility is displayed, as shown in [Figure 3-7](#).

### 3.3.5.1 Test Procedure for CYUSBS234 DVK Configured as SPI

1. To test the functionality of the SPI interface, set up the jumpers as listed in [Table 3-4](#) and shown in [Figure 3-34](#) and [Figure 3-35](#).

Table 3-4. Jumper Settings

S.No	Jumper	Pins to be Shorted	Function
1	J17	2 and 5	SCB_2 (Pin#21) configured for SPI MISO
2	J19	2 and 3	SCB_1 (Pin#20) configured for SPI SSEL
3	J20	2 and 5	SCB_3 (Pin#22) configured for SPI MOSI
4	J21	2 and 3	SCB_4 (Pin#23) configured for SPI SCLK
5	J29	1 and 2	VBUS selection

Figure 3-34. SCB SPI Jumpers






Figure 3-35. VBUS Selection



2. Run the USB Serial Test Utility from **Start > All Programs > Cypress > CYUSBS234 DVK > USBSerialTestUtility**.
3. To use the default Cypress PID, change the **Product ID** to 0004.


**Note** The user has the option to enter custom Vendor ID and Product ID.

Figure 3-36. Test Utility (VID and PID Selection)




4. The test utility lists the interfaces available on the board for the SPI interface. Click **OK**.

Figure 3-37. Test Utility (PID Change)




- Enter an EEPROM Page address within the range specified in the text box (0x0 to 0x3FF) and click the **Write data** button. The status bar at the bottom of window displays the status of the write data operation.

Figure 3-38. Test Utility Data Transfer




- Click the **Read & verify data** button. When the data that is written and read back are identical, a data verification successful message appears.

Figure 3-39. Test Utility Data Transfer Verification



7. Click **OK**. The “Data Verification successful” message appears at the bottom of the window.

Figure 3-40. Test Utility Successful Data Transfer




### 3.3.6 CapSense Configuration

The CY7C65211 USB-Serial bridge controller supports the configurable CapSense functionality, providing best-in-class signal-to-noise ratio (SNR) and water tolerance. This device supports SmartSense™ Auto-Tuning of the CapSense parameters and does not require manual tuning. SmartSense Auto-tuning compensates for printed circuit board (PCB) variations and device process variations. The CYUSBS234 DVK board has one CapSense button to evaluate the CapSense functionality.

Follow these steps to view and modify the parameters for the CapSense configuration:


1. Follow steps 1 to 6 in the section [Connecting CYUSBS234 DVK to Cypress USB-Serial Configuration Utility on page 19](#) to connect the board to the Cypress USB-Serial Configuration Utility.
2. Click the **CapSense®/BCD/GPIO** tab. Click the **Configure** button next to **Enable/Disable CapSense®**.

Figure 3-41. CapSense/BCD/GPIO Configuration Tab



3. To enable the CapSense functionality, check the **Enable CapSense** option. Set **Buttons Needed** to 1, because this board supports one CapSense button denoted as B1 that is assigned to GPIO 11. Assign this GPIO to **Input Sense GPIO** from the drop-down menu adjacent to **Button 1**, as shown in [Figure 3-42](#).

Figure 3-42. CapSense Configuration Editor





You can configure the following CapSense parameters by using the Cypress USB-Serial Configuration Utility:

- a. Enable CapSense
- b. Use as wake-up source
- c. Debounce
- d. Scan Rate
- e. Water Shield
- f. Output activity LED
- g. Buttons needed
- h. Input Sense GPIO
- i. Activity LED GPIO
- j. Sensitivity
- k. Select encoded output GPIO
- l. Auto Assign (Not applicable to this board)

■ **Enable CapSense**

Check this box to enable the CapSense block in the device.

■ **Use as wake-up source**

Check this box to wake up the USB-Serial bridge controller from low-power mode when the CapSense button is touched.

■ **Debounce**

Default Value: 1

Debounce value defines the number of scan cycles (scan rate x number of buttons) a button press needs to be detected by the device before a button press status is reported. For example, if the debounce value is set to two, the device reports a button press status only when it detects the button press for two continuous scan cycles. Debounce ensures that high-frequency high-amplitude noise does not cause false detection of a pressed button. The debounce value can be set to any value between 1 and 5. By default, the debounce value is set to 1.

■ **Scan rate**

Default value: 1 ms

Scan rate is the delay (in ms) between two button scans. For example, if the device has three CapSense buttons and scan rate set to 2 ms, each button will be scanned once every 6 ms. Scan rate can be set to any value between 1 ms and 5 ms. By default, the scan rate is set to 1 ms.

■ **Water shield**

Default value: Disabled

You can enable the waterproofing feature by selecting any GPIO from the drop-down menu. When this feature is enabled, water droplets on the CapSense button will not be considered as finger touch. The waterproofing design uses a concept called "shield", which is a conductor placed around the sensors and is connected to a designated shield pin on the device. The shield must be connected to ground by setting jumper J28 to position 2-3 when not used. In the CYUSBS234 board, GPIO 01 is used for water shield operation and the recommended value of sensitivity is 0.2 pF for waterproofing operation. Set the jumper J28 to position 1-2 and press the reset switch SW3 on the board to test the waterproofing operation.

■ **Output activity LED**

Default value: None



The output activity LED is an indicator for CapSense button touch. You can configure the LED for no indication by setting it to None; one LED for every button by setting it to Individual; or a common LED for more than one CapSense button.

#### ■ Buttons Needed

Default value: 1

This option defines the number of buttons required for a CapSense operation. This device supports five buttons but the board supports one CapSense button.

#### ■ Input Sense GPIO

This option assigns the GPIO to a CapSense button. On this board, the CapSense button is assigned to GPIO 11 for button B1.

#### ■ Activity LED GPIO

Default value: None

This option assigns the GPIO used for the LED indication of the CapSense function. The LED will glow when the assigned CapSense button is touched. On this board, the LED is assigned to GPIO 10.

#### ■ Sensitivity

Default value: 0.2 pF

This option selects the sensitivity of the CapSense button to detect finger touch. You can set the sensitivity to a value between 0.1 pF to 0.4 pF in increments of 0.1 pF. The recommended value for this board is 0.2 pF.

#### ■ Select encoded output GPIO


This option selects the GPIOs that generate a binary-encoded output for an assigned CapSense button. On this board, the encoded output is assigned to GPIO 10 for B1.

#### ■ Auto assign

This option automatically assigns the GPIOs from the available free pool of GPIOs.

4. Click **OK** to close the **Configure CapSense®** window and return to the **CapSense®/BCD/GPIO** tab.
5. After configuring CapSense, click the **Program** button to save the changed CapSense settings. On successful programming, the "Program Succeeded" message appears. Click **OK** to continue.
6. Click the **Disconnect** button to disconnect the board from the configuration utility.
7. Press the reset switch **SW3** on the board. The controller is reinitialized with the new parameters and the board re-enumerates, as shown in [Figure 3-43](#).

Figure 3-43. USB-Serial Bridge Controller Enumeration in Device Manager



8. The Cypress USB-Serial Configuration Utility is displayed, as shown in [Figure 3-7](#).

### 3.3.6.1 Test Procedure for CYUSBS234 DVK Configured for CapSense

1. To test the functionality of the CapSense, set up the jumper as listed in [Table 3-5](#) and shown in [Figure 3-44](#) and [Figure 3-45](#).

Table 3-5. Jumper Settings

Jumper	Pins to be shorted	Function
J28	2 and 3	Waterproofing disabled—Shield is connected to GND
J29	1 and 2	VBUS Selection

Figure 3-44. CapSense Jumper






Figure 3-45. VBUS Selection




2. On the board, press the CapSense button **B1**. The LED D7 glows.
3. To validate CapSense using the Cypress USB-Serial Configuration Utility, follow these steps:
  - ❑ Click the **Launch** button next to **Validate CapSense®**.

Figure 3-46. CapSense Validation




- ❑ Select the **Button Specific Validation** view from the drop-down menu and click the **Load view** button.

Figure 3-47. CapSense Button-specific Validation




- ❑ Select 1 for button **B1** from the drop-down menu against the select button. Select the **RAW count vs Baseline** graph from the drop-down menu. For more information about the options in this window, refer to the *Configuration Utility User Guide.pdf*.
- ❑ The CapSense validation window displays a blue line, which indicates the raw counts without finger touch called the “baseline”. During this event, the button status is OFF.

Figure 3-48. Raw Counts Without Finger Touch



- Touch button B1 with a finger. The CapSense validation window displays a red line, which indicates the raw Counts. During this event, the button status is ON.

Figure 3-49. CapSense Finger Touch Output




### 3.3.7 Battery Charger Detection (BCD) Configuration

The battery charger detection logic in the CY7C65211 device will detect the source of power on the USB port and provides indication over the BCD0 and BCD1 GPIOs.

Follow these steps to view and modify the parameters for BCD configuration:


1. Follow steps 1 to 6 in the section [Connecting CYUSBS234 DVK to Cypress USB-Serial Configuration Utility on page 19](#) to connect the board to the Cypress USB-Serial Configuration Utility.
2. Click the **CapSense®/BCD/GPIO** tab. Click the **Configure** button next to **Battery Charge Detect (BCD)** to launch the **Configure BCD** window.

Figure 3-50. CapSense/BCD/GPIO Configuration Tab



3. To enable the BCD functionality, check the **Enable BCD** option. On this board, BCD1 GPIO 10 is shared by both CapSense and BCD. Disable the CapSense feature (see [CapSense Configuration on page 45](#) for details), if it is already enabled to test the BCD feature of the controller. Assign GPIO 09, GPIO 10, and GPIO 08 to BCD0, BCD1, and Bus Detect pins for this board, using the drop-down menu shown in [Figure 3-51](#).

Figure 3-51. BCD Configuration Settings



**Note** The dead/no battery condition is not supported by the CY7C65211 USB-Serial bridge controller.

Configuring the BCD1 and BCD0 drive mode to High in the BCD mode is not a valid condition for this board. If this condition is enabled, the battery charger IC enters into the Suspend mode.

You can configure the following BCD parameters by using the Cypress USB-Serial Configuration Utility:

- a. Enable BCD
- b. BCD0
- c. BCD1
- d. Bus Detect
- e. BCD Drive mode

#### ■ Enable BCD

Check this option to enable the BCD block in the device.

#### ■ BCD0 and BCD1

You can assign GPIOs to BCD0 and BCD1 from the drop-down menu according to the requirements of the battery charging IC (refer to the battery charging IC datasheet for the truth table).

#### ■ Bus Detect

The Bus Detect pin is used to detect the presence of 5 V on VBUS. You must assign a GPIO to the Bus Detect pin from the drop-down menu to detect the USB connection.

#### ■ BCD Drive mode

The board has a battery charging IC to charge the Li-Ion battery (not included) at various levels, based on the status of BCD0 and BCD1. A truth table must be designed to meet the battery charging current drawn by the battery-charging IC, depending on the source of the USB power.

The battery-charging IC, MAX8856, on the board sets the charging current, as provided in truth table in [Table 3-6](#).



Table 3-6. BCD Drive Mode Truth Table

BCD0/EN1#	BCD1/EN2#	MODE
0	0	100 mA
0	1	500 mA
1	0	750 mA
1	1	Suspend

**Note** Depending on the battery-charging IC that you select, the truth table provided in [Table 3-6](#) will change. You must select a battery-charging IC with two control pins to interface with the USB-Serial bridge controller.

- Click **OK** to close the **Configure BCD** window and return to the **CapSense®/BCD/GPIO** tab.
- After configuring the BCD, click the **Program** button to save the changed BCD settings. On successful programming, the "Program Succeeded" message appears. Click **OK** to continue.
- Click the **Disconnect** button to disconnect the board from the configuration utility.

### 3.3.7.1 Test Procedure for CYUSBS234 DVK Configured for BCD

- To test the functionality of the BCD, set up the jumpers as listed in [Table 3-7](#) and shown in [Figure 3-52](#) and [Figure 3-53](#).

Table 3-7. Jumper Settings

Jumper	Pins to be Shorted	Function
J4	1 and 2	Battery charge enabled - BCD0
J7	1 and 2	Bus detect
J8	1 and 2	Battery charge enabled - BCD1
J29	1 and 2	VBUS Selection

Figure 3-52. BCD Jumpers








Figure 3-53. VBUS Selection



2. Press the reset switch **SW3** on the board. The controller is reinitialized with the new parameters and the board re-enumerates as shown in [Figure 3-54](#).

Figure 3-54. USB-Serial Bridge Controller Enumeration in Device Manager



3. The Cypress USB-Serial Configuration Utility is displayed, as shown in [Figure 3-7](#).  
**WARNING** The SW2 switch should be in position 2-3 before connecting the battery. Use only the recommended rechargeable Li-ion battery. Check the polarity of the battery connector before connecting to the board.
4. Connect a rechargeable Li-ion battery (not supplied with the board) to the battery connector BH1. This board has been tested with a Tenergy Li-Ion 18650 3.7V 2600 mAh rechargeable battery (MPN: 30011-02).
5. Set SW2 in position 1-2.
6. The battery will charge when its voltage is below the nominal voltage (3.7 V), which is indicated by the LED D5.  
**Note** The Li-Ion battery is not provided with the CYUSBS234 DVK board.
7. Set the SW2 switch to position 2-3 and disconnect the battery.


### 3.3.8 CYUSBS234 DVK Restore Default Configuration Settings

The CYUSBS234 DVK board features the CY7C65211 USB-Serial bridge controller, which is factory-programmed for USB-UART bridge and CapSense functionalities. You can reconfigure the device using the Cypress USB-Serial Configuration Utility to meet specific requirements that overwrites the factory configuration.

To restore the board to the factory settings, follow these steps:

1. Follow steps 1 to 6 in the section [Connecting CYUSBS234 DVK to Cypress USB-Serial Configuration Utility on page 19](#) to connect the board to the Cypress USB-Serial Configuration Utility.
2. Click **File > Open Configuration from > Disk**, as shown in [Figure 3-55](#).

Figure 3-55. Select Configuration Window




**Note** The "Restore Default Settings" option will restore the silicon's default settings, which is different from the board default settings.

3. Select the default configuration file from the following location:


```
<Install directory>\Cypress\CYUSBS234 DVK\1.0\default factory settings\CYUSBS234 USB DVK.cyusb
```

Figure 3-56. Select Default Configuration File Window



- After successfully loading the configuration file, the message “Configuration settings were successfully loaded from the file” appears. Click **OK** to continue.

Figure 3-57. Load Configuration



5. Click **Program** to update the configuration settings. On successful programming, the "Program Succeeded" message appears. Click **OK** to continue.
6. Click **Disconnect** to disconnect the board from the configuration utility and press the reset switch **SW3** on the board.
7. The Cypress USB-Serial Configuration Utility is displayed as shown in [Figure 3-7](#); the board enumerates as shown in [Figure 3-5](#).

## 4. Hardware




### 4.1 Board Details

The CYUSBS234 DVK board consists of the following components:

- CY7C65211 USB-Serial bridge controller
- Power-supply system
- USB connector
- Serial communication block
  - SCB jumpers
  - RS-232 line driver for UART Interface
  - I2C EEPROM for I2C Interface
  - SPI EEPROM for SPI Interface
  - GPIO Header
- CapSense button
- Li-Ion battery charger
- Reset switch
- LEDs


Figure 4-1. CYUSBS234 DVK Board



## 4.2 Theory of Operation

This section provides the block-level description of the CYUSBS234 DVK board.

Figure 4-2. Hardware Block Diagram



The CY7C65211 is a full-speed USB-Serial bridge controller that offers a configurable serial channel for UART/I2C/SPI interface. This device also integrates the industry-leading CapSense technology (for touch-sensitive key switches) and the USB-IF Battery Charging specification ver. 1.2 (to detect the power source on the USB port). This device is a fixed-function controller, which does not require any changes to the firmware on the embedded products, because the parameters of the controller and serial channels can be modified using an easy-to-use Cypress USB-Serial Configuration Utility.

The CYUSBS234 DVK board communicates through the USB to configure the CY7C65211 USB-Serial bridge controller. The board can function as a USB to UART/I2C/SPI bridge. This board also showcases the CapSense and BCD functionalities. The board has a RS-232 line driver, I2C EEPROM, and SPI EEPROM to demonstrate the USB-UART, USB-I2C, and USB-SPI bridge functionalities respectively. This board has a set of jumpers that must be configured according to the UART/I2C/SPI functionality. For more information about the jumpers, see [SCB Jumpers on page 66](#). The board has a reset switch, which connects to the XRES pin of the CY7C65211 USB-Serial bridge controller and a touch-sensitive button to demonstrate CapSense. This board also has a battery-charging IC to charge the Li-ion battery, which is connected to the battery connector to demonstrate BCD.

You can power the board from a USB standard-A to micro-B cable, DC power supply, or battery. This board is designed to work at 5 V. The board has two switches; switch SW1 is used to select either self-powered or bus-powered mode and switch SW2 is used to connect the external Li-ion battery to the battery charging circuit.



## 4.3 Functional Description

This DVK uses the CY7C65211 USB-Serial bridge controller, a full-speed USB controller that enables seamless PC connectivity for peripherals with serial interfaces, such as UART, SPI, and I2C. CY7C65211 also integrates CapSense and BCD-compliant with the USB Battery Charging Specification, Rev. 1.2. It integrates a voltage regulator, an oscillator, and flash memory for storing configuration parameters, offering a cost-effective solution. The CY7C65211 device supports bus-powered and self-powered modes and enables efficient system power management with suspend and remote wake-up signals. It is available in a 24-pin QFN package. For more information, refer to the USB-Serial web page at [www.cypress.com/go/usbserial](http://www.cypress.com/go/usbserial) and the USB-Serial datasheet.

### 4.3.1 Features

- USB 2.0-certified, Full-Speed (12 Mbps)
  - Supports communication driver class (CDC), personal health care device class (PHDC), and vendor-specific drivers
  - BCD compliant with USB Battery Charging Specification, Rev. 1.2 (Peripheral Detect only)
  - Integrated USB termination resistors
- Single-channel configurable UART interface
  - Data rates up to 3 Mbps
  - 256 bytes for each transmit and receive buffer
  - Data format:
    - 7 to 8 data bits
    - 1 to 2 stop bits
  - No parity, even, odd, mark, or space parity
  - Supports parity, overrun, and framing errors
  - Supports flow control using Clear To Send (CTS), Request To Send (RTS), Data Terminal Ready (DTR), Data Set Ready (DSR)
- Single-channel configurable SPI interface
  - Master/slave up to 3 MHz
  - Data width: 4 bits to 16 bits
  - 256 bytes for each transmit and receive buffer
  - Supports Motorola, TI, and National Semiconductor SPI modes
- Single-channel configurable I2C interface
  - Master/slave up to 400 kHz
  - 256 bytes each transmit and receive buffer
  - Supports multi-master I2C
- CapSense
  - SmartSense Auto-tuning enabled

### 4.3.2 Power-Supply System


The power-supply system on this board is designed to be powered-up from one of the following input sources:

- External 5-V DC power supply (Self-powered operation)
- Power from USB bus (Bus-powered operation)
- Battery power supply

The USB-Serial bridge controller on this board is powered by 3.3 V. The onboard Low Drop Out regulator provides the required 3.3 V, with input from one of the above sources.

- The board is powered by 5-V DC power supply when:
  - 5-V DC power supply is plugged in DC power jack (J1)
  - SW1 is set to position 1-2
  - SW2 can be set to any position
- The board is powered by USB power supply when:
  - USB standard-A to micro-B cable is plugged in micro-B connector(J2)
  - SW1 is set to position 2-3
  - SW2 can be set to any position
- The board is powered from the battery power supply when:
  - Li-ion rechargeable battery is connected in BH1 connector.
  - SW2 is set to position 1-2
  - SW1 is set to position 2-3

Figure 4-3. Power Supply Block Diagram



### 4.3.3 LEDs

The CYUSBS234 DVK board has six LEDs. D2 and D4 LEDs indicate the power status. The D7 LED indicates CapSense finger touch on button B1, the D5 LED indicates battery charging operation, and D8 and D10 LEDs indicate the activity on the TXD and RXD lines of the UART.

Figure 4-4. LED D2 (5-V Power Supply Status)




Figure 4-5. LED D4 (3.3-V Power Supply Status)




Figure 4-6. LED D5 (Battery Charging Indication)



Figure 4-7. LED D7 (CapSense Touch Indication)






Figure 4-8. LEDs D8 and D10 (Tx and Rx Activity Indication)



#### 4.3.4 USB Connector

A USB standard micro-B connector is used on the board. The shield of this USB connector is connected to the ground and two inductors (L3 and L4) are placed on VBUS and GND pins to reduce the noise from power supply lines. ESD protection is provided on the D+, D-, and VBUS lines.

Figure 4-9. USB Connector



### 4.3.5 Serial Communication Block (SCB)

The CY7C65211 USB-Serial bridge controller integrates an SCB block that can be configured for UART, I2C or SPI interfaces. The board incorporates an RS-232 line driver (U5) and a DB-9 connector (J15) to evaluate the UART functionality. EEPROM (U7) and EEPROM (U8) are used to evaluate the I2C and SPI functionalities on the CYUSBS234 DVK respectively. As an option, these onboard devices can be disconnected (using J17-J22) and the serial interface signals can be made available on header J23 for external connectivity.

#### 4.3.5.1 SCB Jumpers


This board has six SCB jumpers: J17, J18, J19, J20, J21, and J22. These jumpers must be configured for USB to UART/I2C/SPI operation. These jumpers are grouped as 3/4/5 pins configurations.

[Table 4-1](#) provides the jumper configuration details.

Table 4-1. Jumper Configuration for SCB(UART/I2C/SPI/GPIO)

Functionality	J17	J18	J19	J20	J21	J22
UART	2-4	2-1	2-4	2-4	2-4	2-1
I2C	2-3			2-3		
SPI	2-5		2-3	2-5	2-3	
GPIO Header	2-1	2-3	2-1	2-1	2-1	2-3


Figure 4-10. SCB Jumpers



#### 4.3.5.2 RS-232 Interface

This board has a RS-232 line driver and a DB9 connector for RS-232 interface, with a maximum baud rate of 1 Mbps (limited by the RS-232 line driver). The board includes two LED indicators: D10 for RXD and D8 for TXD activity.

Figure 4-11. RS-232 Interface






#### 4.3.5.3 I2C Interface

The CY7C65211 USB-Serial bridge controller's SCB pins can be configured for I2C. These pins are brought out on jumpers J17 and J20 to provide I2C interface. The board has a dedicated I2C slave EEPROM to evaluate the I2C interface. The CY7C65211 USB-Serial bridge controller is configured as an I2C master. The I2C pins (SCL and SDA) can be brought out on the external header J23 by putting the jumper on position 1-2 of J17 and J20.


Figure 4-12. I2C Interface



#### 4.3.5.4 SPI Interface

The CY7C65211 USB-Serial bridge controller's SCB pins can be configured for SPI. These pins are brought out on jumpers J17, J19, J20, and J21 to provide a SPI interface. The board has a dedicated SPI slave EEPROM to evaluate the SPI interface. The CY7C65211 USB-Serial bridge controller is configured as a SPI master. The SPI pins (SSEL, MISO, MOSI, and SCLK) can be brought out on the external header J23 by putting the jumper on position 1-2 of J17, J19, J20, and J21.

Figure 4-13. SPI Interface



#### 4.3.5.5 GPIO Header

The CY7C65211 USB-Serial bridge controller's SCB pins can be configured as GPIO. These pins are brought out on external header J23. Seven pins on this header (J23.1, J23.2, J23.3, J23.5, J23.7, J23.8, and J23.9) can be used as I/O pins and the two pins J23.4 and J23.6 have fixed functions for "Suspend" and "Wakeup". See [USB Configuration on page 21](#) for more details on Suspend and Wakeup. J23.10 on the GPIO header is the GND pin.

Figure 4-14. GPIO Header




Table 4-2. GPIO Headers


CY7C65211 Pin	Default Configuration	UART Configuration	SPI Configuration	I2C Configuration	External Configuration
1	SCB_0	RXD			GPIO_6
20	SCB_1	DSR#	SSEL_OUT		GPIO_2
21	SCB_2	RTS#	MISO_IN	SCL_OUT	GPIO_3
22	SCB_3	CTS#	MOSI_OUT	SDA	GPIO_4
23	SCB_4	TXD	SCLK_OUT		GPIO_5
2	SCB_5	DTR#			GPIO_7

#### 4.3.6 CapSense Button

The board has one CapSense touch button B1, which is connected to GPIO\_11 and a Cmod (modulation) capacitor connected to pin GPIO\_0. This board hardware supports the waterproofing feature of CapSense. When the waterproofing feature is enabled, the water droplets on the sensor will not be sensed. This helps to prevent any accidental sensing of the button due to water droplets.

Waterproofing feature enables a shield electrode to compensate for the water drops influence on the sensor at the hardware level. This electrode is located around the sensing electrodes. When water film is present on the device overlay surface, the coupling between the shield and sensing electrodes is increased. The shield electrode allows to reduce the influence of parasitic capacitance, which gives more dynamic range for processing sense capacitance changes. This shield must be connected to a designated shield pin on the device to function or must be connected to the ground when not used. On the board, the shield can be connected to the designated shield pin (GPIO\_1) by setting jumper J28 (position 1-2) and can be connected to ground by setting jumper J28 (position 2-3). Refer to the CapSense Design Guide for further details related to CapSense.

Figure 4-15. CapSense Schematic



#### 4.3.7 Battery Charger Detection


The CY7C65211 USB-Serial bridge controller integrates battery charging detection, which is compliant with the USB-IF Battery Charging Specification, Rev 1.2. This device detects the source of power on the USB port and provides voltage indication (logic high or logic low) over BCD0 and BCD1 pins to select the different battery charging modes. The BCD0 and BCD1 pins are connected to EN1# and EN2# of the battery charging IC MAX8856. Depending on the BCD0 and BCD1 logic, the different charging modes are selected, as given in Table 4-3. The board is designed with a Li-ion battery charger IC (MAX8856) that has two logic inputs (EN1#, EN2#) to control the amount of current drawn from the USB source to charge the battery. For more details about the battery charger operation, refer to the chip (MAX8856) datasheet.

Table 4-3 shows the amount of current drawn in different modes by the battery charging IC.

Table 4-3. MAX 8856 (Battery Charging IC) BCD Drive Modes

EN1#	EN2#	MODE
0	0	100 mA
0	1	500 mA
1	0	750 mA
1	1	Suspend


### Figure 4-16. Battery Charger Circuit



### 4.3.8 Reset Switch

The reset switch is connected to the XRES pin of the CY7C65211 USB-Serial bridge controller and is used to reset the device. A reset is required when a new set of configuration parameters are programmed.

Figure 4-17. Reset Schematic



## 5. Additional Information



### 5.1 Using USB-Serial on a Mac OS

**Note** The CYUSBS234 DVK board should be configured for USB to UART, I2C, or SPI on Windows OS before using on Mac OS.


#### 5.1.1 Using CYUSBS234 DVK in Communications Device Class (CDC) Mode

The CY7C65211 USB-Serial bridge controller automatically binds to the AppleUSBCDC driver, which is the CDC class driver in Mac OS X.

Follow these steps to use the CDC mode for Cypress USB-Serial UART on a Mac OS:

1. Connect the CYUSBS234 DVK board to Mac. The Mac CDC class driver (AppleUSBCDC) automatically binds to the device. After the driver successfully binds, a device node is created as `/dev/tty.usbmodem<number>`.
2. Install a standard terminal emulator, such as SerialTools to test the UART functionality of the device. SerialTools is available in the Apple App Store.
3. Open the SerialTools application. In the **Serial port** option, select the Cypress USB-Serial UART device node created in step 1.


Figure 5-1. Connecting USB-Serial in SerialTools



4. Configure the UART settings, such as baud rate, stop bits, data width, and parity.
5. For simple loopback tests, short the RXD and TXD pins on the DVK.

6. Click **Connect** to start communication with the device.
7. Type **Cypress** in the text field. Because the local echo is always enabled in the SerialTools application, the entered characters will be displayed twice.

Figure 5-2. SerialTools Application: Loopback Test Output



### 5.1.2 Using the CYUSBS234 DVK board in Vendor Mode

Follow these steps to use the CYUSBS234 DVK board in the Vendor mode on a Mac OS.

1. Download the latest *USB-Serial SDK for Mac* from [www.cypress.com/go/usbserial](http://www.cypress.com/go/usbserial).
2. Follow the steps listed in the README file provided in the software development kit (SDK) to compile and install the library.
3. When the library is installed, execute the test utility (CyUSBSerialTestUtility) to verify the communication with the CYUSBS234 DVK board.
4. For a detailed API description, refer to *CyUSBSerial API Documentation.pdf* in the <Install Directory>/common/doc folder of the SDK.



# A. Appendix



## A.1 Schematic

The schematic for CYUSBS234 DVK board is available at <http://www.cypress.com/go/CYUSBS234>.

Figure A-1. Schematic




Figure A-2. Schematic




Figure A-3. Schematic




Figure A-4. Schematic





Figure A-5. Schematic




## A.2 CY7C65211 USB-Serial Design Guidelines

This section explains the design guidelines for using the CY7C65211 USB-Serial bridge controller:

- The CY7C65211 silicon can operate from 1.71 V to 5.5 V.
- Short the VCCD pin to the VDDD pin when the operating voltage (VDDD) is from 1.71 V to 1.89 V.
- Connect a 1-uF decoupling capacitor between the VCCD pin and ground when the operating voltage is greater than 2 V.
- Place decoupling capacitors close to VDDD pins. In this board, C14, C15, C16, and C17 are the decoupling capacitors that are placed close to the VDDD pins. C10 is a 1-uF capacitor to be placed close to the VCCD pin, as shown in [Figure A-6](#).

Figure A-6. Decaps and CMOD Capacitor Placement



- The CY7C65211 USB-Serial bridge controller has an exposed pad (EPad) in the bottom that must be connected to the GND pad on the PCB.
- An active low 1-μs pulse width is required to reset the CY7C65211 USB-Serial bridge controller.
- Do not provide pull-up resistors on SPI pins, except SSEL.
- Provide pull-up resistors on I2C pins.
- USB traces (DP/DM) should be routed with 90-Ohms impedance.
- USB differential traces (DP/DM) should be routed with solid reference plane.
- ESD protection device must be placed closer to the USB connector.
- In the BCD interface, the bus detect signal should be connected with a resistor divider network from VBUS. Refer to the *Application Examples* section in the CY7C65211 datasheet for recommended values.
- No plane or traces should be present under CapSense buttons in any layer.
- The CapSense pad should have 10- mm diameter.
- The CapSense button-to-ground spacing should be 20 mils.
- The typical hatching for the ground fill is 25% on the top layer (7-mil trace, 45-mil spacing) and 17% on the bottom layer (7-mil trace, 70-mil spacing).
- Ensure that the solder mask is enabled for CapSense pads.
- The CapSense trace and the water shield trace should be 7 mils in thickness.

- Route the CapSense trace in the gnd layer (inner layer) of the bottom layer, so that it is isolated from the external noise. On the top layer, because the traces are exposed, bringing a hand near the trace causes false triggers.
- The hatched GND should be extended along the full length of the CapSense trace routing.
- The CapSense trace should have a 560-ohms resistor that must be placed close to the silicon.
- The CMOD capacitor (2.2 nF) must be placed close to the silicon pin.
- The CMOD capacitor should be of Chip-On-Glass (COG) type.
- Make sure there is no test point or headers on the CapSense and CMOD traces.
- The gap between the ground and the sensor pad should be equal to the overlay thickness, but not less than 0.5 mm and not more than 2 mm.
- There must not be any solid ground around or beneath the sensor pad and sensor traces. Solid ground increases the sensor capacitance.
- The CapSense button shape should be a solid round pattern or a rectangle with curved edges.
- The button-to-button spacing must be 8 mm.
- The via hole size on the CapSense trace must be 10 mil. A maximum of 2 vias are allowed on the CapSense trace.

For more information, refer to [Getting Started with CapSense](#) at the Cypress website.

The following figures show the typical CapSense interface circuit and layout:

Figure A-7. CapSense Interface Circuit




Figure A-8. CapSense Layout - Top Layer




Figure A-9. CapSense Layout - GND Layer




Figure A-10. CapSense Layout - Power Layer





Figure A-11. CapSense Layout - Bottom Layer





## A.3 Troubleshooting Guide

Table A-1. Troubleshooting Guide

Problem	Possible cause	Possible solution
The CYUSBS234 DVK board does not power up in BUS powered mode. Power ON LED, D2 (5V) and D4 (3.3V) do not light up.	USB Cable is not connected to PC.	Connect the USB cable.
	PC does not power up the USB port.	Connect on a different USB port.
	USB cable is faulty	Use different USB cable. Or use the Self power mode and connect 5-V DC power supply provided with the kit.
	Power ON LED is faulty.	Check the voltage on the D2 LED (TP17) is 5 V and the voltage on D4 LED (TP10) is 3.3 V
The CYUSBS234 DVK board does not power up in Self power mode. Power ON LED (D2 - 5V, D4 - 3.3V) does not light up.	Power adapter is faulty.	Check the voltage output from power supply adapter. It should be approximately 5-V DC. If the power adapter is faulty, use the USB to power the board.
	Power ON LED is faulty.	Check the voltage on the D2 LED (TP17) is 5 V and the voltage on D4 LED (TP10) is 3.3 V
The CYUSBS234 DVK board does not enumerate.	USB driver is not bound to the DVK.	Run <i>setup.exe</i> in following location: a. <Install_directory>\Cypress\CYUSB S234 DVK\1.0\driver\cyusb3 b. <Install_directory>\Cypress\CYUSB S24 DVK\1.0\driver\cyusbserial
	Jumper J29 is not fitted.	Set the jumper J29 to 1-2. Set J7 jumper if the device is configured for BCD.
SCB configured as UART does not work.	One of these jumpers (J17, J18, J19, J20, J21 and J22) is not set correctly for UART configuration.	Set the jumpers as mentioned in the section <a href="#">3.3.3.1 Test Procedure for CYUSBS234 DVK Configured as UART on page 28</a> of this kit guide.
	UART is not properly configured.	Load <i>CYUSBS234 USB DVK.cyusb</i> , supplied with the kit. Refer to the section <a href="#">3.3.8 CYUSBS234 DVK Restore Default Configuration Settings on page 56</a> . Press the <b>RESET</b> switch to update the new configuration.
SCB configured as I2C does not work.	One of these jumpers (J17 and J20) is not set correctly for I2C configuration.	Set the jumpers as mentioned in the section <a href="#">3.3.4.1 Test Procedure for CYUSBS234 DVK Configured as I2C on page 35</a> of this kit guide.
	I2C is not properly configured	Load <i>cyusbs234 i2c config.cyusb</i> supplied with the kit. Refer to the section <a href="#">3.3.8 CYUSBS234 DVK Restore Default Configuration Settings on page 56</a> . Press the <b>RESET</b> switch to update the new configuration.
SCB configured as SPI does not work.	One of these jumpers (J17, J19, J20, and J21) is not set correctly for SPI configuration.	Set the jumpers as mentioned in the section <a href="#">3.3.5.1 Test Procedure for CYUSBS234 DVK Configured as SPI on page 42</a> of this kit guide.
	SPI is not properly configured.	Load <i>CYUSBS234 SPI_BCD.cyusb</i> supplied with the kit. Refer to the section <a href="#">3.3.8 CYUSBS234 DVK Restore Default Configuration Settings on page 56</a> . Press the <b>RESET</b> switch to update the new configuration.

Table A-1. Troubleshooting Guide (continued)

Problem	Possible cause	Possible solution
CapSense button does not work.	Jumper J28 is not set correctly for CapSense configuration.	Set the jumper J28 in 2-3 for normal CapSense operation, and in 1-2 for water proofing operation.
	CapSense is not properly configured.	Load <i>CYUSBS234 USB DVK.cyusb</i> , supplied with the kit. Refer to section 3.3.8 <a href="#">CYUSBS234 DVK Restore Default Configuration Settings on page 56</a> . Press the <b>RESET</b> switch to update the new configuration.
Battery charging does not work.	One of these jumpers (J4, J7, and J8) is not set correctly for BCD configuration. Position of the SW2 is not correct.	Set the jumpers as mentioned in section 3.3.6.1 <a href="#">Test Procedure for CYUSBS234 DVK Configured for CapSense on page 49</a> . Set SW2 to position 2-3.
	Battery is dead.	Replace the battery.
	BCD is not configured correctly.	Load <i>CYUSBS234 SPI_BCD.cyusb</i> supplied with the kit. Refer to section 3.3.8 <a href="#">CYUSBS234 DVK Restore Default Configuration Settings on page 56</a> . Press the <b>RESET</b> switch to update the new configuration.
Test utility does not work. (Test utility hangs after write data operation)	SPI or I2C configuration jumpers are not set correctly.	Set the jumpers as mentioned in <a href="#">“Test Procedure for CYUSBS234 DVK Configured as SPI” on page 42</a> and <a href="#">“Test Procedure for CYUSBS234 DVK Configured as I2C” on page 35</a> .

## A.4 Bill of Materials (BoM)

Table A-2. Bill of Materials

Item	Qty	Reference	Description	Manufacturer	Mfr Part Number
1	1	600-60114-01 REV**	PCB, CYUSBS234 USB-Serial Board	Cypress Semiconductor	600-60114-01 REV**
2	1	BH1	CONN HEADER 2POS 1.25MM VERT TIN	Molex Inc	0530470210
3	1	C1	CAP ALUM 330UF 25V 20% SMD	Panasonic	EEE-1EA331UP
4	1	C2	CAP TANT 22UF 25V 20% 2917	Kemet	T496X226M025AT
5	2	C3,C16	CAP TANT 10UF 16V 20% 1206	AVX Corporation	TAJA106M016RNJ
6	1	C4	CAP TANT 100UF 10V 20% 1210	AVX Corporation	TAJB107M010RNJ
7	1	C7	CAP TANT 330UF 10V 10% 2917	AVX Corporation	TAJD337K010RNJ
8	3	C8,C9,C19	CAP CER 4.7UF 16V 10% X5R 0603	Taiyo Yuden	EMK107ABJ475KA-T
9	1	C10	CAP CER 1UF 16V 20% X5R 0402	TDK Corporation	C1005X5R1C105M
10	1	C14	CAP CER 2.2UF 16V 10% X5R 0603	TDK Corporation	C1608X5R1C225K/0.80
11	12	C15,C20,C22,C25,C27,C29,C30,C33,C34,C37,C38,C46	CAP CER 0.1UF 16V 10% X7R 0402	Yageo	CC0402KRX7R7BB104
12	2	C17,C26	CAP CER 10000PF 16V 10% X7R 0402	Kemet	C0402C103K4RACTU
13	2	C18,C21	CAP TANT 4.7UF 25V 20% 1206	Kemet	T491A475M025AT
14	2	C23,C24	CAP CER 22UF 10V 10% X7R 1206	Murata	GRM31CR71A226KE15L
15	1	C41	CAP CER 2200PF 50V 5% NP0 0603	Murata Electronics North America	GRM1885C1H222JA01D
16	1	D1	DIODE SCHOTTKY 4A 40V SMB	Micro Commercial Co	SK44BL-TP
17	5	D2,D4,D5,D6,D7	LED GREEN CLEAR 0603 SMD	Lite-On Inc	LTST-C190KGKT
18	2	D8,D10	LED GREEN RECT CLEAR 0603	Lite-On Inc	LTST-C193KGKT-5A
19	1	J1	CONN PWR JACK 2.1X5.5MM HIGH CUR	CUI Inc	PJ-102AH
20	1	J2	CONN RCPT 5POS R/A MICRO USB	JAE Electronics	DX4R005J91R1500
21	4	J3,J4,J7,J8	CONN HEADER 2POS .100" SNGL GOLD	Samtec Inc	TSW-102-08-G-S
22	1	J15	CONN DB9 MALE .318" R/A NICKEL	Norcomp Inc	182-009-113R531
23	2	J17,J20	CONN HEADER 5POS .100" SNGL GOLD	Samtec Inc	TSW-105-08-G-S
24	4	J18,J22,J28,J29	CONN HEADER 3POS .100" SNGL GOLD	Samtec Inc	TSW-103-08-G-S
25	2	J19,J21	CONN HEADER 4POS .100" SNGL GOLD	Samtec Inc	TSW-104-08-G-S
26	1	J23	CONN HEADER 10POS .100" DL GOLD	Samtec Inc	TSW-105-08-G-D
27	3	L2,L3,L4	FERRITE CHIP 220 OHM 0805	Murata	BLM21PG221SN1D
28	2	R1,R9	RES 180 OHM 1/10W 5% 0603 SMD	Vishay Dale	CRCW0603180RJNEA
29	2	R2,R3	RES 68.0 OHM 1/8W 1% 0805 SMD	Panasonic	ERJ-6ENF68R0V
30	1	R5	RES 100K OHM 1/10W 5% 0603 SMD	Vishay/Dale	CRCW0603100KJNEA
31	10	R7,R44,R46,R48,R49,R50,R51,R52,R63,R65	RES 0.0 OHM 1/10W 0603 SMD	Panasonic	ERJ-3GEY0R00V
32	1	R8	RES 23.7K OHM 1/10W 1% 0603 SMD	Panasonic	ERJ-3EKF2372V
33	1	R10	RES 10.0K OHM 1/10W 1% 0603 SMD	Panasonic	ERJ-3EKF1002V
34	1	R11	RES 19.6K OHM 1/10W 1% 0603 SMD	Panasonic	ERJ-3EKF1962V
35	1	R12	RES 100 OHM 1/8W 1% 0603 SMD	Stackpole Electronics Inc	RNCP0603FTD100R
36	3	R13,R16,R18	RES 270 OHM 1/10W 5% 0603 SMD	Panasonic	ERJ-3GEYJ271V
37	1	R14	RES 560 OHM 1/10W 1% 0603 SMD	Panasonic	ERJ-3EKF5600V
38	3	R20,R21,R22	RES 10.0K OHM 1/10W 1% 0603 SMD	Panasonic	ERJ-3EKF1002V
39	2	R23,R24	RES 2.2K OHM 1/10W 5% 0603 SMD	Panasonic	ERJ-3GEYJ222V

Table A-2. Bill of Materials (continued)

Item	Qty	Reference	Description	Manufacturer	Mfr Part Number
40	1	R25	THERMISTOR NTC 47K 1% 0603	Vishay BC Components	NTCS0603E3473FHT
41	1	R26	RES 91.0K OHM 1/10W 1% 0603 SMD	Panasonic	ERJ-3EKF9102V
42	4	R53,R54,R55,R57	RES 4.70K OHM 1/10W 1% 0603 SMD	Panasonic	ERJ-3EKF4701V
43	2	R66,R67	RES 0.0 OHM 1/10W JUMP 0402 SMD	Panasonic	ERJ-2GE0R00X
44	2	SW1,SW2	SWITCH SLIDE MINI SPDT PCMNT SLV	C&K Components	1101M2S3CQE2
45	1	SW3	SWITCH TACTILE SPST-NO 0.02A 15V	Panasonic	EVQ-PAC07K
46	6	TP6,TP10,TP16,TP17,TP18,TP19	TEST POINT PC MINI .040"D RED	Keystone Electronics	5000
47	4	TP11,TP12,TP13,TP14	TEST POINT PC MINI .040"D Black	Keystone Electronics	5001
48	1	U1	USB-Serial Dual Channel UART/I2C/SPI bridge with CapSense and BCD	Cypress Semiconductor	CY7C65211-24LTXI
49	1	U2	IC REG LDO 3.3V 1A SOT-89-5	ON Semiconductor	NCP694H33HT1G
50	1	U3	IC BATT CHARGER LI+ 1CELL 14TDFN	Maxim Integrated	MAX8856ETD+T
51	1	U4	IC ESD PROTECTION LO CAP SOT23-6	STMicroelectronics	USBLC6-2SC6
52	1	U5	IC TXRX RS-232 1MBPS SD 28TSSOP	Maxim Integrated	MAX3245EEUI+
53	1	U7	IC EEPROM 128KBIT 400KHZ 8SOIC	Microchip Technology	24LC128-I/SM
54	1	U8	IC EEPROM SPI BUS 2MB 8SOIC	STMicroelectronics	M95M02-DRMN6TP
No Load Components					
55	1	B1			
56	1	C5	CAP TANT 100UF 10V 20% 1210	AVX Corporation	TAJB107M010RNJ
57	1	C6	CAP TANT 330UF 10V 10% 2917	AVX Corporation	TAJD337K010RNJ
58	1	C42	CAP TANT 4.7UF 25V 20% 1206	Kemet	T491A475M025AT
59	1	C43	CAP CER 2.2UF 16V 10% X5R 0603	TDK Corporation	C1608X5R1C225K/0.80
60	1	C44	CAP CER 0.1UF 16V 10% X7R 0402	Yageo	CC0402KRX7R7BB104
61	1	C45	CAP CER 10000PF 16V 10% X7R 0402	Kemet	C0402C103K4RACTU
62	1	C47	CAP CER 10PF 50V 10% NP0 0402	Kemet	C0402C100K5GACTU
63	4	R29,R33,R56,R58	RES 4.70K OHM 1/10W 1% 0603 SMD	Panasonic	ERJ-3EKF4701V
64	1	R47	RES 0.0 OHM 1/10W 0603 SMD	Panasonic	ERJ-3GEY0R00V
65	1	R64	RES 100K OHM 1/10W 5% 0603 SMD	Vishay/Dale	CRCW0603100KJNEA
66	6	TP1,TP2,TP3,TP7,TP9,TP15			
Install On Bottom of PCB As Close To Corners As Possible					
71	4	Bumpers	BUMPER CLEAR.370X.19" CYLINDER	Richco Plastic Co	RBS-35BK
Special Jumper Installation Instructions					
72	11	NA	Headers and Wire Housings MINI JUMPER GF 13.5 CLOSE TYPE BLACK	Kobiconn	151-8030-E
Bag and Tag					
73	1	Caution Label	"Caution: Use only recommended rechargeable Li-ion Battery. Check polarity of battery connector."		Caution LBL
74	1	ESD Label	LBL, PCBA Anti-Static Warning, 10mm X 10mm	Cypress Semiconductor	899-60014-01
75	1	PCBA Label	LBL for PCBA 121-60096-01, with barcode	Cypress Semiconductor	

# AMEYA360

Components Supply Platform

Authorized Distribution Brand :



Website :

Welcome to visit [www.ameya360.com](http://www.ameya360.com)

Contact Us :

➤ Address :

401 Building No.5, JiuGe Business Center, Lane 2301, Yishan Rd  
Minhang District, Shanghai , China

➤ Sales :

Direct     +86 (21) 6401-6692  
Email       amall@ameya360.com  
QQ         800077892  
Skype       ameyasales1 ameyasales2

➤ Customer Service :

Email       service@ameya360.com

➤ Partnership :

Tel         +86 (21) 64016692-8333  
Email       mkt@ameya360.com